

FI-CAB42812-SVR-OPW-NR

NETWORK ROOM



FI 42U 800MM X 1200MM SERVER CABINET BUILT TO OPW NETWORK ROOM SPEC BELOW:

- 1 X BOLTED ALUMINIUM FRAME CONSTRUCTION
- 1 X BESPOKE ** OPW SPEC ** ROOF
- ** 2 X 450MM X 80MM BRUSH STRIP CUT OUTS - 1 CENTRALLY EITHER SIDE & 1 X STANDARD 300 X 80MM CUT OUT TO REAR OF ROOF **
- ** 2 X 100MM X 100MM CUT OUT IN EACH REAR CORNER OF ROOF FOR PDU'S **
- ** 100MM X 100MM CUT OUTS TO HAVE 2 PART GLAND PLATE TO CLAMP AROUND 1X 32AMP CABLE - 17MM DIAMETER CENTRAL TO 2 PART PLATE **
- 1 X CURVED MESH (83% AIRFLOW) DOOR, 3 POINT LOCKING SYSTEM AND COMBI LOCK
- 1 X WARDROBE MESH (83% AIRFLOW) DOOR, 3 POINT LOCKING SYSTEM AND COMBI LOCK
- 1 X PAIR OF BESPOKE 70/30 SPLIT SLIDING PANELS –
- ** OFFSET SO RETURN FOLDS DO NOT CLASH WITH REAR OF CENTRAL CABLE TRAY **
- 4 X UNIVERSAL STYLE ADJUSTABLE MOUNTING PROFILES
- ** U HEIGHT NUMBER LABELS ON ALL PROFILES **
- ** FRONT PROFILES SET 100MM BACK FROM FRONT OF ALUMINIUM **
- ** REAR PROFILES SET 740MM FROM FRONT PROFILES **
- NO MID PROFILES
- 2 X HORIZONTAL AIR BAFFLE PLATES FITTED AT TOP AND BOTTOM OF PROFILES
- 2 X ** FINGER STYLE ** 42U 300MM CABLE TRAY (1 FITTED CENTRALLY EACH SIDE)
- 2 X ** FINGER STYLE ** 42U 100MM CABLE TRAY (1 FITTED EITHER SIDE AT REAR OF CABINET)
- 2 X PAIR OF SINGLE DEAD SPACE PDU BRACKETS
- 3 X 1U JUMPER RING (IDF DESIGN) FITTED TO INSIDE OF TOP REAR ALI HORIZONTAL
- 1 X 42U EARTH BAR
- 1 X BAYING KIT
- 1 X EARTH BONDING KIT
- 1 X SET OF HEAVY DUTY CASTORS
- 1 X ** BESPOKE ** SET OF ADJUSTABLE CABINET FEET
- ** FEET TO HAVE 20MM THREAD **
- ** CABINET AND ACCESSORIES TO BE SPRAYED RAL 9003 **